

160'-0"

# PROPOSED SITE PLAN

411 RD 2 WEST

41'-0

78'-0

41'-0

270'-0"

PROPOSED SINGLE  
FAMILY DWELLING

1000 Gallon  
with Filter  
TANK

4" PVC 50R35

EXISTING  
TO  
DEMO

S.F.D.  
EXISTING  
FOR  
DEMO

8 RUNS  
@  
40'

50'

16'

40'

116'-0"

MANTEL

50'

50'

10'

8 Runs of 40' A/Rc Infiltrators 84"  
Min 5' spacing at center  
36" Septic Sand For Leaching Bed 40'x50'  
12" Septic Sand For Mantle 50'x50'  
Tracer Wire For perimeter of Leaching Bed  
and Header to Septic tank