

Lakeshore West Water Pollution Control Plant

Existing System

- The Lakeshore West WPCP is a Wastewater Treatment Facility servicing the Primary Settlement Area of Kingsville.
- The Plant is located at the intersection of Conservation Blvd and County Road 50.
- The Plant has a rated capacity of 5,400 m³/day.





Environmental Assessment

Alternative Solutions

EA Process has identified 4 alternative solutions:

Option 1 – Improve efficiency of existing Plant processes.

Option 2 – Upgrade Plant and decommission the lagoons.

Option 3 – Upgrade Plant and use lagoons as storage.

Option 4 – Upgrade lagoons.

Option 3 & 4 brought forward to MECP for discussion on June 12, 2025.

Alternative Solution #3

Upgrade Plant & Upgrade Lagoons to an Equalization Tank

Proposed Solution:

- Upgrades and expansion to the Plant.
- Connect lagoons to the Plant by a new forcemain.
- Lagoons would act as a large storage tank.
- All effluent discharges to Lake Erie.

Benefits:

- No discharge to Wagle Creek, lower regulatory risk.
- Standard technology, quicker implementation.

Next steps to understand:

- Effluent requirements, coordinate with MECP.



Alternative Solution #4

Upgrade Lagoons

Proposed Solution:


- Upgrade the lagoon treatment technology.
- Effluent from Plant continues to discharge to Lake Erie.
- Effluent from lagoons discharges to Wigle Creek.

Benefits:

- Reduces upgrades required at the Plant.
- Marginally lower capital costs.

Implementation concerns:

- Assimilative Capacity Study of Wigle Creek required by MECP, may take up to 2 years to complete.
- Capacity Study and MECP may conclude that this is not a viable option due to low base flows in Wigle Creek.



Timeline



Next Steps for this EA Project:

Task	Estimated Timeline
Select Final Preferred Alternative Solution (Option 3 selected)	July 2025 ✓
Public Information Center	Sept 2025
Phase 3 Report – Alternative Design Concepts Report to provide types of treatment options	Sept 2025
Phase 4 Report – Summary of all previous EA deliverables	Oct 2025
Address any report updates	Nov 2025
Completion of EA Project	Dec 2025

If the Town Proceeds with Upgrades:

A sample schedule from detailed design through to construction, contingent on Council and funding approvals.

Task	Estimated Timeline
Hire a Consulting Engineer	2026
Start Detailed Design	2026
ECA Application to MECP start at the 40-60% of detailed design phase	2026/2027
Finish Detailed Design	2027
Retain a Contractor	2028
Start Construction	2028